

DAV PUBLIC SCHOOL

Danibigha, Aurangabad (Bihar)-824101

TENDER NOTICE

Sealed Quotations/Bids are being invited from interested parties through registered post/by hand for **construction of Yagyashala** in the campus of D.A.V. Public School, Danibigha, Aurangabad. For specification and other details please visit the school website i.e. **<https://davdanibigha.com>** or the School's Notice Board.

The school keeps its right reserved to cancel the tender any time. Last date of receiving the tender is within the 10 days from the publishing of tender notice.

Name of the Work	Construction of Yagyashala
Time of Completion of proposed work	20 days
Date of Tender Notification	29/03/2024
Last Date/Time for receipt of Bids	07/04/2024
Name and address of official who inviting Tender	Headmistress, DAV Public School, Danibigha, Aurangabad (Bihar)- 824101
Contact Numbers	9608862226, 8789248663

Mrs. Alpana Mishra
Headmistress

Ref No: DAV Danibigha/2023-24/610

dated: 28/03/2024

TOTAL AREA			452.0	SQFT
1	20.3 20.3.1	Boring, providing and installing cast-in-situ Single under-reamed pile below pile cap in cement concrete M25 excluding the cost of steel reinforcement all complete 300 mm	24.4	m
2	2.6	Earth work in Excavation including disposal of excavated soil upto 50 m in all kinds of soil	6.8	Cu m
3	2.28	Supplying and filling in plinth with Local sand including watering, ramming, consolidating and dressing complete	1.3	Cu m
4	11.72	Providing designation 100A one brick flat soling joints filled with local sand complete	20.0	Sq m
5	4.1.3	Providing PCC (1:2:4) with graded Stone chips of 20 mm nominal size excluding the cost of centring and shuttering all works in Foundation all complete	3.9	Cu m
6	5.1.2	Providing and Laying in Position RCC M20 with graded stone chips of 20 mm nominal size all works upto plinth level excluding the cost of centering, shuttering and reinforcement	16.9	Cu m
7	6.1.12/1	Fly ash Brick work with cement mortar (1:4) in Foundation & Plinth	3.7	Cu m
8	5.9	Centring and shuttering including strutting, propping etc. and removal of form		
	5.9.1	Foundation	10.7	Sq m
	5.9.6	Column	33.0	Sq m
	5.9.7	Steps	64.0	Sq m
	5.9.20	Slab	40.0	Sq m
	5.9.21	Band, Beam	379.2	Sq m
9	5.22	Reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete		
	5.22.7B	TMT - 10 mm	372.5	Kg
	5.22.7C	TMT - 12 mm	1,116.0	Kg
10	13.12.1	15 mm (1:3) cement Plaster finished with a floating coat of neat cement over plinth all complete	10.5	Sq m

11	13.11.4	12 mm (1:6) cement Plaster	209.6	Sq m
12	8.2.2.2	Providing and fixing 18 mm thick Granite floor over 20 mm thick cement mortar (1:4) including moulding and polishing all complete	40.0	Sq m
13	11.23.1	18 mm thick marble flooring over 20 mm base in cement mortar (1:4) including rubbing and polishing all complete Makrana white second quality.	35.0	Sq m
14	11.30.1	40 mm thick fine dressed stone flooring over 20 mm (average) thick base with joint finished flush:base 1:5 (1 cement: 5 coarse sand)with joints 3 mm thick, side buttered with cement mortar 1:2 (1 cement : 2 stone dust) admixed with pigment to match the shade of stone and pointing with same mortar. Red sand stone	13.3	Sq m
15	13.78.1	Providing one coat of cement primer of approved brand and manufacture on wall surface all complete	209.6	Sq m
16	13.79.1	Providing water proof cement paint of approved brand and manufacture and of required shade to give and even shade three or more coat on new work all complete	209.6	Sq m