

Ref No.....

Date.....

**ABSTRACT OF COST FOR PAINTING OF COMPLETE BUILDING AT D A V PUBLIC SCHOOL, DANIBIGHA, AURANGABAD, BIHAR**

		<b>GROUND FLOOR</b>			
		total ceiling painting area	5265	SQFT	hall, guest room and few classrooms not included since they have been recently painted
		total Wall area	11809	SQFT	
		window/doors area	1914	SQFT	2 times for both sides
		corridor grill area	936	SQFT	
		<b>FIRST FLOOR</b>			
		total ceiling painting area	9683	SQFT	3 classrooms and composite lab not included
		total Wall area	15980	SQFT	
		window/doors area	5976	SQFT	2 times for both sides
		corridor grill area	840	SQFT	
		<b>SECOND FLOOR</b>			
		total ceiling painting area	10810	SQFT	computer lab not included
		total Wall area	17640	SQFT	
		window/doors area	5976	SQFT	2 times for both sides
		corridor grill area	840	SQFT	
		<b>THIRD FLOOR</b>			
		total ceiling painting area	10810	SQFT	library not included
		total Wall area	17640	SQFT	
		window/doors area	5976	SQFT	2 times for both sides
		corridor grill area	840	SQFT	
		<b>STAIRCASE</b>			
		Flight bottom	1344	SQFT	
		total Wall area	5184	SQFT	
		section of tread riser	85	SQFT	
		metal railing	480	SQFT	
		<b>EXPOSED BEAMS IN CEILING</b>			
		exposed beam bottom painting area in class and corridor	7650	SQFT	
		<b>MUMTY AND PARAPET</b>			
		total ceiling painting area	504	SQFT	
		total Wall area	920	SQFT	
		Parapet	5744	SQFT	
		window/doors area	88	SQFT	
		<b>EXTERIOR AND PLINTH</b>			
		total painting area (G+3+PLINTH)	37230	SQFT	
		Projections (columns and chajjas)	10120	SQFT	
		<b>TOTAL INTERIOR AREA TO BE PAINTED</b>	<b>91106</b>	<b>SQFT</b>	
		<b>TOTAL EXTERIOR AREA TO BE PAINTED</b>	<b>50558</b>	<b>SQFT</b>	
		<b>TOTAL ENAMEL PAINTING</b>	<b>23866</b>	<b>SQFT</b>	

S.NO	S.O.R	DESCRIPTION	Qty.	Unit.	Rate	Amount
1	MR	Removing white or colour wash by scrapping and sand paper in and preparing the surface smooth including necessary repair scratches etc. complete (including labour cost and scaffolding if required)			lumsum	
		<b>INTERIOR PAINTING</b>				
		Area of interior painting in SQFT	91106	SQFT		
		Area of interior painting in SQM	8467	SQM		
2		Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade:				
		two or more coats	8467	Sq M		0
		<b>EXTERIOR PAINTING OF BLOCK</b>				
		Area of Exterior painting in SQFT	50558	SQFT		
		Area of Exterior painting in SQM	4699	SQM		
3		paint of required shade :				
		New work (Two or more coat applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm) <b><u>(since the old work has completely faded and new painting has to be done as good as new)</u></b>	4699	SqM		0
		<b>ENAMEL PAINTING</b>				
		Area of enamel painting	23866	SQFT		
		Area of enamel painting	2218	SQM		
4		Painting with synthetic enamel paint of approved brand and manufacture to give an even shade:One or more coats on old work.	2218	SqM		0
			TOTAL			

NOTE

1. Rates are inclusive of G.S.T.
2. Hall, principals chamber, guest room, library and 6 classrooms painting not included since these have been painted recently
3. computer lab and composite lab painting not included since they have to be painted later; separately
4. boundary painting has not been included in this estimate since its already included with boundary repair work in a separate estimate